

Work Order ID 86835

86835

Page 1

July-06-12 3:08:00 PM

Item ID: D3262-1

Accept

N900040100

Setup Start ***NS1***

Revision ID:

Stop ***NS2***

Item Name: Tube

Start Date: 7/06/12 Start Qty: 5.00

~~*5*~~ 6

Cust Item ID:

Required Date: 7/06/12 Req'd Qty: 5.00

~~*5*~~ 6

Customer:

Reference:

Approvals:

Process Plan:

Date: 2079

Tooling:

Date:

QC:

Date:

SPC (Y/N):

Date:

Run Start ***NR1***

Stop ***NR2***

Sequence ID/ Work Center ID	Operation Description	Set Up/ Run Hours	Tool ID	Tool #	Plan Code	Accept Qty	Reject Qty	Reject Number	Insp. Stamp
Draw Nbr	Revision Nbr								
D3262	Rev E								
110		0.00							
110	Small Fab								
Large Fab	Memo	0.00							
Large Fab	1- Cut as per dwg 2- Deburr								
120		0.00							
120	QC6- Inspect dimensions to drawing								
QC	Memo	0.00							
Quality Control									
140		0.00							
140	Identify as per dwg & Stock Location: <u>WMA</u>								
Packaging	Memo	0.00							
Packaging									

~~5~~ 6 ~~0~~ Ac
12.07.11

5.12.12/12

~~5~~ 6 ~~0~~ 12
12.07.12

6 ~~0~~ 12
12.07.16

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Work Order ID 86835***86835***

Page 2

July-06-12 3:08:00 PM

Item ID: D3262-1

Accept

N900040100Setup Start ***NS1***

Revision ID:

Stop ***NS2***

Item Name: Tube

Start Date: 7/06/12 Start Qty: 5.00 ***5***

Cust Item ID:

Required Date: 7/06/12 Req'd Qty: 5.00 ***5***

Customer:

Reference:

Approvals: Process Plan: _____ Date: _____ Tooling: _____ Date: _____

Run Start ***NR1***

QC: _____ Date: _____ SPC (Y/N): _____ Date: _____

Stop ***NR2***Sequence ID/
Work Center IDOperation
DescriptionSet Up/
Run Hours

Tool ID

Tool #

Plan
CodeAccept
QtyReject
QtyReject
NumberInsp.
Stamp

150

QC21- Final Inspection - Work Order Release

0.00

150

QC

Memo

0.00

Quality Control

12/7/18 *[Signature]*

[Signature]
12-07-18

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Picklist Print

July-06-12 3:08:00 PM

Page 1

Work Order ID: 86835

Parent Item: D3262-1

Parent Item Name: Tube

Start Date: 7/06/12

Required Date: 7/06/12

Start Qty: 5.00

Required Qty: 5.00

Comments: IPP C05.03.10Removed P/O for liquid penetrant inspectionKJ/JLM IPP RevD: revise process
DD 10.01.27 verified byEC IPP Rev:E as
per ECN10-571 DD 10.05.10 verified :EC

Component Item ID/ Item Name	Replacement Item ID	Mfg/ Purch	Bin Item	Primary Location	Last Location	Route Seq ID	Unit of Measure	Qty on Hand	Qty per Kit	Total Qty	Qty Issued	Date Issued	Status
M6061T6T5.000W.125 6061-T6 Tube 5.00 X.125W		Purchased	No			110	f	23.6263	0.94	4.9473684		12.07.11	

Location

MAT028

Loc Qty

23.62631554

Loc Code

115112
121558

3.62631554
20

3.96
0.94

Dart Aerospace Ltd

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector




Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____
 Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

ITEM	QTY -041	P/N	DESCRIPTION
	X	D3262-041	CANISTER ASSEMBLY
1	1	D3262-1	TUBE
2	2	D3262-3	CAP

SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. 86835 1/2079



D3262-041 CANISTER ASSEMBLY

RELEASED
2010-05-07
NA

NOTES:

- 1) MATERIAL: N/A
- 2) FINISH: CHEMICAL CONVERSION COAT PER QSI 005 4.1
POWDER COAT ASSEMBLY WHITE (4.3.5.1) PER DART QSI 005 4.3
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: IDENTIFY WITH DART P/N "D3262-041" AND B/N USING FINE POINT PERMANENT INK MARKER
- 7) WEIGHT: 2.51 lbs
- 8) LIQUID PENETRANT INSPECT PER ASTM E1417 LEVEL 1 OR
PRESSURIZE TO 10 psi AND SUBMERGE UNDER WATER TO CHECK FOR LEAKS

E	0.25 WAS 0.45 (ZNC7-4, C7-5); 0.13 WAS 0.33 (ZN B7-4, B7-5); ADD DIMENSION (ZN B1-4, D1-5, B1-5)	RF	10.05.03
D	ADD D3262-043-5 (ZN B5-2; B5-5); REVISE DIMENSIONS TO EQUAL TOOL DIMENSIONS (ZN B2-4; C2-4) PER CAR 09-004	RF	09.12.30
C	Ø5.165 WAS Ø5.190	RF	06.08.31
B	ADD PRESSURE TESTING OPTION	MB	05.02.14
A	NEW ISSUE	RF	04.05.06
REV.	DESCRIPTION	BY	DATE
DESIGN	RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
DRAWN	RF	DRAWING NO.	REV. E
CHECKED	<i>[Signature]</i>	D3262	SHEET 1 OF 5
MFG. APPR.	<i>[Signature]</i>	TITLE	SCALE
APPROVED	<i>[Signature]</i>	FUEL PURGE CANISTER	NTS
DE APPR.	<i>[Signature]</i>	DATE 10.05.03	
COPYRIGHT © 2004 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.			

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector



Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

ITEM	QTY	P/N	DESCRIPTION
	X	D3262-043	CANISTER ASSEMBLY
1	1	D3262-1	TUBE
2	2	D3262-5	CAP



D3262-043 CANISTER ASSEMBLY

NOTES:

- 1) MATERIAL: N/A
- 2) FINISH: CHEMICAL CONVERSION COAT PER QSI 005 4.1
POWDER COAT ASSEMBLY WHITE (4.3.5.1) PER DART QSI 005 4.3
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: IDENTIFY WITH DART P/N "D3262-043" AND B/N USING FINE POINT PERMANENT INK MARKER
- 7) WEIGHT: 2.50 lbs
- 8) LIQUID PENETRANT INSPECT PER ASTM E1417 LEVEL 1 OR
PRESSURIZE TO 10 psi AND SUBMERGE UNDER WATER TO CHECK FOR LEAKS
- 9) WELD CAPS WITH 3/4-16 TAP TOP HOLE IN LINE WITH 9/16-18 TAP BOTTOM HOLE

DESIGN	RF	DART AEROSPACE LTD	
DRAWN	RF	HAWKESBURY, ONTARIO, CANADA	
CHECKED	RF	DRAWING NO. D3262	REV. E
MFG. APPR.	RF	SHEET 2 OF 5	
APPROVED	RF	TITLE	SCALE
DE APPR.	RF	FUEL PURGE CANISTER	NTS
DATE	10.05.03	<small>COPYRIGHT © 2004 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL, AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.</small>	



W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries



D3262-1 TUBE

NOTES:

- 1) MATERIAL: 6061-T6 OR 6061-T62 ALUMINUM TUBING, 5.00 OD x 0.125 WALL
PER WW-T-700/6 OR AMS 4080 OR AMS 4082 OR QQ-A-200/8 OR QQ-A-225/8
REF. DART SPEC. M6061T6T5.000W.125
- 2) FINISH: NONE
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: NONE
- 7) WEIGHT: 1.96 lbs
- 8) PART IS SYMMETRICAL ABOUT CENTERLINE

DESIGN	RF	DART AEROSPACE LTD	
DRAWN	RF	HAWKESBURY, ONTARIO, CANADA	
CHECKED	<i>[Signature]</i>	DRAWING NO.	REV. E
MFG. APPR.	<i>[Signature]</i>	D3262	SHEET 3 OF 5
APPROVED	<i>[Signature]</i>	TITLE	SCALE
DE APPR.	<i>[Signature]</i>	FUEL PURGE CANISTER	NTS
DATE	10.05.03	<small>COPYRIGHT © 2004 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD</small>	

RELEASED
2010-05-03
[Signature]

86835

Dart Aerospace Ltd


W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____


Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			


NOTE: Date & initial all entries



SECTION A-A C5-4



D3262-3 CAP



DETAIL B C7-4
SCALE 2X

NOTES:

- 1) MATERIAL: 6061-T6/T651 ALUMINUM BAR
PER QQ-A-200/8 OR QQ-A-225/8
REF. DART SPEC. M6061T6B
- 2) FINISH: NONE
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: ENGRAVE 'DART' LOGO AS SHOWN USING 0.75 HIGH x 0.010 DEEP
(MAX) LETTERS WITH TOOL RADIUS OF 0.25 MIN
- 7) WEIGHT: 0.28 lbs
- 8) PART IS SYMMETRICAL ABOUT CENTERLINE

DESIGN	RF	DART AEROSPACE LTD	
DRAWN	RF	HAWKESBURY, ONTARIO, CANADA	
CHECKED	RF	DRAWING NO.	REV. E
MFG. APPR.	RF	D3262	SHEET 4 OF 5
APPROVED	RF	TITLE	SCALE
DE APPR.	RF	FUEL PURGE CANISTER	NTS
DATE	10.05.03	<small>COPYRIGHT © 2004 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.</small>	

RELEASED
2010-05-03
AM

76835


W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____


Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			


NOTE: Date & initial all entries




SECTION C-C D5-5



D3262-5 CAP



DETAIL D C7-5
SCALE 2X



DETAIL E B7-5
SCALE 2X

RELEASED
2010-05-07
NW

NOTES:

- 1) MATERIAL: 6061-T6/T651 ALUMINUM BAR
PER QQ-A-200/8 OR QQ-A-225/8
REF. DART SPEC. M6061T6B
- 2) FINISH: NONE
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: ENGRAVE 'DART' LOGO AS SHOWN USING 0.75 HIGH x 0.010 DEEP
(MAX) LETTERS WITH TOOL RADIUS OF 0.25 MIN
- 7) WEIGHT: 0.27 lbs
- 8) PART IS SYMMETRICAL ABOUT CENTERLINE

DESIGN	RF	DART AEROSPACE LTD	
DRAWN	RF	HAWKESBURY, ONTARIO, CANADA	
CHECKED	RF	DRAWING NO.	REV. E
MFG. APPR.	RF	D3262	SHEET 5 OF 5
APPROVED	RF	TITLE	SCALE
DE APPR.	RF	FUEL PURGE CANISTER	NTS
DATE	10.05.03	COPYRIGHT © 2004 BY DART AEROSPACE LTD	
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.			

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr.	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries